

ANNAN TO GRETNA RAILWAY
Gabions**Trackside**

An 800m long stretch of track duelling required the existing cutting to be widened and gabions were selected to provide the support.

The gabion wall was constructed in-situ with our PTS trained operatives, who were sponsored by Carillion.

Some 1450m³ of gabion walling was completed in 7 weeks

Gabion Type – 3mmØ woven gabion unit

Height – Up to 3m High

**Maccaferri Construction Ltd**

Riverview House
Friarton Road, Perth
Scotland. PH2 8DF
T: 01738 492620
F: 01738 492639

E: enquiries@macconstruct.co.uk

Web: www.maccaferri-construction.co.uk

Other Offices**Oxford**

T: 01865 7770555 F: 01865 774550 E: oxford@maccaferri.co.uk

Belfast:

T: 028 9026 2830 F: 028 9026 2849 E: belfast@maccaferri.co.uk